

1. Objective

Deploy a website on Aws EC2(t3.small) using Linux and Nginx

2. Aws Service Used

EC2 = Virtual Server

Security Group = Firewall

Key Pair = Authentication

Public IP = Access website

3. Linux Command

`sudo apt-get update`

`sudo apt-get install nginx-y`

`sudo systemctl status nginx`

`sudo systemctl restart nginx`

`df -h`

`free -m`

`ps -ef`

`top`

`htop`

4. Problem Faced

Permission denied while SSH

Solved using `chmod 400`

Port 80 blocked

Solved by allowing HTTP in SG

Nginx not opening

Restared service using

`Sudo systemctl restart nginx`

Docker permission denied

Solve `sudo usermod -aG docker $USER`

5. Learning

Created an EC2 instance

Connected using ssh

Installed nginx

Used GitHub

Learned Basic Linux command

Hosted Website

Configured Security Group

6. Time Taken

25-30 min

7. ScreenShots

EC2 dashboard

Security Group

SSH login

Nginx Status

Browser Output

Github Repository

8. Bonus

- 1 . create another SG
2. install docker and run
3. create shell script to restart nginx